




INSTALLATION INSTRUCTIONS FOR Z1201-XB WATER CLOSET SYSTEM





 Make sure the carrier is properly bolted to the flooring using four anchor bolts. One in each foot and two in the rear anchor bar. See Figure 1.


Note: See installation instructions (Form #C51) found in the Z1201-XH Trim Kit for more information on installation.




Prep for finished wall. Install the (4) threaded rods into the front of the faceplate (see Figure 2a) until each rod extends 5/8" past the closet bowl flange (see Figure 2b). Use (4) Jam Nuts from the 66955-332-9 hardware bag to lock the threaded rods in place. See Figure 2a.

Note: If the studs are too long they will bottom out in the finishing cap nut, preventing proper gasket compression which may result in leakage.

3. Add (4) Jam Nuts on to the threaded rods so that the front of the nut is 1/4" behind the finish wall. See **Figure 3**.





▲ WARNING: Cancer and Reproductive Harm - www.P65Warnings.ca.gov

▲ ADVERTENCIA: Cáncer y daño reproductivo - www.P65Warnings.ca.gov

▲ AVERTISSEMENT: Cancer et effets néfastes sur la reproduction - www.P65Warnings.ca.gov

Zurn Industries, LLC | Specification Drainage Operation

1801 Pittsburgh Avenue, Erie, PA U.S.A. 16502 · Ph. 855-663-9876, Fax 814-454-7929

In Canada | Zurn Industries Limited


3544 Nashua Drive, Mississauga, Ontario L4V 1L2 · Ph. 905-405-8272, Fax 905-405-1292

Rev. B
Date: 04/10/18
C.N. No. 139851
Form # C52




INSTALLATION INSTRUCTIONS FOR Z1201-XB WATER CLOSET SYSTEM

4 Place the Support Frame Assembly (P1201-XB, P.N. 830080019) on the threaded rods. Make sure that the frame sets on all four jam nuts. Adjust Jam Nuts so that the front of the frame is 1/16" out from the finished wall. See carrier cross section shown in Figure 4.




Once the Support Frame Assembly is on the studs, thread the vertical threaded rods down until they set firmly on the floor. See **Figure 5a**.

Make sure that the horizontal threaded rods are setting on the front frame assembly. See **Figure 5b**.




6 Tighten the (2) nuts on each vertical threaded rod. See **Figure 6**.



7 Assemble a fiber washer and cap nut, from the 66955-292-9 hardware bag, onto each rod and hand tighten. Secure closet with an additional halfturn using a wrench on each nut to complete the installation. See **Figure 7**.

Note: The closet should not make contact with the finished wall.

Note: If using a vitreous china water closet, use Z1200-ADJ-NUT.



1801 Pittsburgh Avenue, Erie, PA U.S.A. 16502 · Ph. 855-663-9876, Fax 814-454-7929